



COST SAVINGS

SUSTAINABLE

TIME SAVER

NO HEAVY EQUIPMENT

QUALITY MATERIALS

“Surefoot’s aim is to inform all industries that there are better, faster, cleaner and easier alternatives than using concrete.”

T150 Residential

Bolting pattern:
147 mm x 3 x 16mm holes

Micro Piles:
3 x 32NB (Nominal Bore) 42.4OD
Galvanised Pipe Light, Medium, Heavy

Load capacity:
Up to 25kN

Average installation time:
10 minutes approx



SF250-4w Residential

Bolting pattern:
140 centres x 4 x 22 slotted holes

Micro Piles:
4 x 32NB (Nominal Bore) 42.4OD
Galvanised Pipe - 4mm wall

Load capacity: Up to 110kN

Average installation time: 10 minutes

Micropile direction configuration option:
2 way, 3 way, 4 way



SF250-6w Residential

Bolting pattern:
140 centres x 4 x 22 slotted holes

Micro Piles:
6 x 32NB (Nominal Bore) 42.4OD
Galvanised Pipe - 4mm wall

Load capacity: Up to 150kN

Average installation time: 15 minutes



SF400-6w Residential

Bolting pattern:
198-250 PCD x 4 x 22mm holes
300-350 PCD x 4 x 26mm holes

Micro Piles:
6 x 32NB (Nominal Bore) 42.4OD
Galvanised Pipe - 4mm wall

Load capacity: Up to 160kN

Average installation time: 15 minutes



SF400-8w Residential / Commercial

Bolting pattern:
198-250 PCD x 4 x 22mm holes
300-350 PCD x 4 x 26mm holes

Micro Piles:
8 x 32NB (Nominal Bore) 42.4OD
Galvanised Pipe - 4mm wall

Load capacity: Up to 200kN

Average installation time: 20 minutes




SF400-12w Commercial

Bolting pattern:
198-250 PCD x 4 x 22mm holes
300-350 PCD x 4 x 26mm holes

Micro Piles:
12 x 32NB (Nominal Bore) 42.4OD
Galvanised Pipe - 4mm wall

Load capacity: Up to 250kN

Average installation time: 25 minutes




SF500 Commercial

Bolting pattern:
233-300 PCD x 4 x 22mm holes
350-400 PCD x 4 x 26mm holes

Micro Piles:
12 x 32NB (Nominal Bore) 42.4OD
Galvanised Pipe - 4mm wall

Load capacity: Up to 300kN

Average installation time: 30 minutes approx




SF600 Commercial

Bolting pattern:
350-400 PCD x 4 x 26mm holes
432-500 PCD x 4 x 32mm holes

Micro Piles:
16 x 32NB (Nominal Bore) 42.4OD
Galvanised Pipe - 4mm wall

Load capacity: Up to 360kN

Average installation time: 40 minutes approx



Surefoot load capacities are indicative and are dependent on soil type and pile embedment depth, for specification, please contact Surefoot directly.